

VULCRAFT/VERCO GROUP ACOUSTICAL PERFORMANCE TEST REPORT

SCOPE OF WORK

ASTM E90 AND ASTM E492 TESTING ON CERAMIC TILE ON 5 MM ECOSILENCE UNDERLAYMENT

SPECIMEN TYPE

Vulcraft 20 Gage Dove Tail 3.50 Steel Deck with Gypsum Board Ceiling

REPORT NUMBER

H7787.12-113-11-R0

TEST DATE

02/17/18

ISSUE DATE

04/05/18

RECORD RETENTION END


02/17/22

PAGES

13

DOCUMENT CONTROL

ATI 00629 (09/19/17) RTTDS-R-AMER-Test-2844 © 2017 INTERTEK





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

REPORT ISSUED TO

VULCRAFT/VERCO GROUP

7205 Gault Avenue North Fort Payne, Alabama 35967

SECTION 1

SCOPE

Intertek Building & Construction (B&C) was contracted by to perform testing in accordance with ASTM E90 AND ASTM E492 on Ceramic Tile on 5 mm ECOsilence Underlayment. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted in the VT test chambers at Intertek B&C located in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

SECTION 2

SUMMARY OF TEST RESULTS

DATA FILE NO.	H7787.12
SERIES/MODEL:	Ceramic Tile on 5 mm ECOsilence Underlayment
STC	56
IIC	49

COMPLETED BY: Jason P. Taylor **COMPLETED BY:** Jordan Strybos Technician II - Acoustical Project Manager - Acoustical TITLE: **Testing** TITLE: **Testing SIGNATURE: SIGNATURE: DATE:** 04/05/18 DATE: 04/05/18

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of ACCREDITED the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 3

TEST METHODS

The specimen was evaluated in accordance with the following:

ASTM E90-09 (2016), Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

ASTM E413-16, Classification for Rating Sound Insulation

ASTM E492-09(2016)e1, Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine

ASTM E989-06 (2012), Classification for Determination of Impact Insulation Class (IIC)

ASTM E2235-04 (2012), Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods

SECTION 4

MATERIAL SOURCE/INSTALLATION

The full test specimen was assembled on the day of testing by B&C. All materials provided by the client were installed on an existing B&C assembly (Vulcraft 20 Gage Dove Tail 3.50 Steel Deck with Gypsum Board Ceiling) utilizing B&C-supplied materials. The assembly was installed in a steel test frame which was installed into the opening between the source and receive rooms in the test chamber. The test frame was isolated from the structure with dense neoprene gasket.

The total weight of the floor/ceiling assembly was 3473.7 kg. B&C will store samples of the test specimen for four years. Photographs of the test specimen are included in the attachments. A drawing of the test specimen is included in the attachments.

B&C will service this report for the entire test record retention period. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by B&C for the entire test record retention period.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 5

EQUIPMENT

INSTRUMENT	MANUFACTURER	MODEL	DESCRIPTION	ASSET #	CAL DAT	Έ
Data Acquisition Unit	National Instruments	PXI-1033	Data Acquisition Card	63763-1	06/16	*
Data Acquisition Unit	National Instruments	PXI-4462	Input Card	63763-4	07/16	*
Data Acquisition Unit	National Instruments	PXI-4462	Input Card	63763-5	06/16	*
Microphone Calibrator	Norsonic	1251	Pistonphone calibrator	INT00127	03/17	
Receive Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	65617	05/17	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63744	05/17	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63745	05/17	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63746	63746 09/17	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63747	05/17	
Receive Room Environmental	Comet	T7510	Temperature and Humidity	63810	10/17	
Indicator	Comet	17510	Transmitter	63811	10/17	
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63738	04/17	
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63739	04/17	
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63740	04/17	
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63742 04/17		
Source Room Microphone	PCB Electronics	378B20	Microphone and Preamplifier	63741 04/17		
Source Room Environmental Indicator	Comet	T7510	Temperature and Humidity Transmitter	INT00603	NT00603 03/17	
Tapping Machine	Norsonic	Nor277	Tapping Machine	INT00936	936 12/17	

^{*} The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

VT RECEIVE ROOM VOLUME	158.86 m³
VT SOURCE ROOM VOLUME	190 m ³

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Jason P. Taylor	Intertek B&C
Jordan Strybos	Intertek B&C

Version: 09/19/17 RTTDS-R-AMER-Test-2844 Page 4 of 13



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 7

TEST PROCEDURE

The microphones were calibrated before conducting the tests. The air temperature and relative humidity conditions were monitored and recorded during all measurements.

The airborne transmission loss test was conducted in accordance with the ASTM E90 test method using the single direction method. Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions. Four sound pressure level measurements were made simultaneously in both rooms, at each of five microphone positions.

The impact sound transmission test was conducted in accordance with the ASTM E492 test method. Two background noise sound pressure level, two sound pressure level measurements with the tapping machine operating at each position specified by ASTM E492, and five sound absorption measurements were conducted at each of five microphone positions.

Detailed test procedures, data for flanking limit tests, repeatability measurements, and reference specimen tests are available upon request.

SECTION 8

TEST CALCULATIONS

The STC (Sound Transmission Class) and IIC (Impact Insulation Class) ratings were calculated in accordance with ASTM E413 and ASTM E989, respectively.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 9

TEST SPECIMEN DESCRIPTION

MATERIAL	DIMENSIONS (mm/inch)	THICKNESS (mm/inch)	MANUFACTURER AND SERIES	QUANTITY	AVERAGE WEIGHT		
	304.8 by 304.8	8.5	Daltile	10.98 m²	15.72 kg/m²		
Ceramic Tile	and wiped clean. 254 mortar on the	The ceramic tile w e underlayment. T	as placed into the 6.35 mm jo as placed with light pressure he mortar was set using a 6.3 to cure to manufacturer's sp	onto a bed of Lati 35 mm by 6.35 mm	crete Platinum		
	3023 by 1219	5.0	ECOsilence	10.98 m²	4.2 kg/m²		
Rubber Underlayment	adhesive. The und	derlayment was ad a 0.79 mm by 1.59	plastic was adhered to the fl lhered to the sheeting with E mm by 0.79 mm trowel. Ad	CORE™ EGrip™ III	adhesive, which		
Standard 4000	3023 by 3632	152.4	N/A	10.98 m²	270.63 kg/m²		
PSI Concrete	Note: Poured directly on the floor deck and allowed to cure for a minimum of 28 days.						
	3023 by 609.6	152.4	20 Gage Vulcraft Dove Tail 3.50	10.98 m²	12.01 kg/m²		
Steel Deck Note: Installed per manufacturer's specifications in a test frame with the top of the c with the source room. All seams and gaps underneath the deck were plugged with be sealed with Pecora AC-20 Acoustical Sealant.							
25 Gage Furring	3023 by 63.6	38.1	ClarkDietrich	21.16 lin m	0.98 kg/m		
Channel	1	Note: The furring channels were attached directly to the bottom of the steel deck, spaced 610 mm on center. The measured steel thickness was 1.2 mm.					
Communication Desired	1219 by 3023	15.9	USG SHEETROCK® Brand FIRECODE® C Core	10.98 m²	11.91 kg/m²		
Gypsum Panel	Note: Fastened with 25.4 mm fine thread drywall screws on 610 mm centers. Seams and perimeter sealed with Pecora AC-20® Acoustical Sealant and covered with pressure-sensitive tape.						



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 10

TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS



EDE O	BACKGROUND	ADCODDTION	SOURCE	RECEIVE	SPECIMEN	95%	NUMBER
FREQ	SPL	ABSORPTION	SPL	SPL	TL	CONFIDENCE	OF
(Hz)	(dB)	m²	(dB)	(dB)	(dB)	LIMIT	DEFICIENCIES
80	30.1	17.7	110	71	37	3.2	-
100	27.5	17.3	105	68	36	1.8	-
125	26.1	11.6	105	69	36	1.6	4
160	22.8	11.6	107	69	37	0.8	6
200	23.2	10.3	105	67	38	1.4	8
250	32.7	11.5	104	59	46	0.9	3
315	18.7	10.4	106	58	48	0.8	4
400	20.4	8.9	105	53	53	0.4	2
500	21.3	7.8	103	49	56	0.3	0
630	16.7	7.4	105	49	58	0.4	0
800	18.1	7.4	104	47	58	0.6	0
1000	16.5	7.2	104	46	61	0.3	0
1250	14.6	7.2	104	44	62	0.3	0
1600	15.2	7.6	104	42	63	0.5	0
2000	15.6	8.4	104	42	63	0.5	0
2500	14.7	9.4	102	38	65	0.5	0
3150	13.3	10.6	104	34	70	0.5	0
4000	12.0	12.1	104	32	72	0.4	0
5000	11.0	13.9	104	28	75	0.4	-
6300	11.0	18.0	98	18	78	0.5	-
8000	11.6	23.6	97	14	80	0.6	-
10000	12.2	30.5	92	11	77	0.7	-
STC Rati	ng 56	(Sound Transm	ission Class,)	Sum	of Deficiencies	27

Notes:

¹⁾ Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.

²⁾ Specimen TL levels listed in red are potentially limited by the laboratory flanking limit.

³⁾ Specimen TL levels listed in <u>blue</u> indicate the lower limit of the transmission loss.

⁴⁾ Specimen TL levels listed in green indicate that there has been a filler wall correction applied



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP


Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 11

TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS GRAPH

DATA FILE NO. CLIENT DESCRIPTION	4000 PSI Concrete	ramic Tile, 5 mm ECOsi e, 152.4 mm 20 Gage Vu Gage Furring Channel, 1	ulcraft Dove 1	ail 3.50 Steel Deck, 3	8.1 mm
SPECIMEN AREA		Receive Temp.		Source Temp.	19°C
TECHNICIAN	JPT	Receive Humidity	57%	Source Humidity	57%





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 12

TEST RESULTS - IMPACT SOUND TRANSMISSION

TEST DATE DATA FILE NO. CLIENT DESCRIPTION	4000 PSI Concrete	ramic Tile, 5 mm ECOsi e, 152.4 mm 20 Gage Vu Gage Furring Channel, 1	ulcraft Dove 1	Tail 3.50 Steel Deck, 3	8.1 mm	
SPECIMEN AREA	, ,	···				
TECHNICIAN	JPT	Max. Humidity	57%	Min. Humidity	56%	

FREQ	BACKGROUND	ABSORPTION	NORMALIZED IMPACT SP		NUMBER
,	SPL			CONFIDENCE	OF
(Hz)	(dB)	m ²	(dB)	LIMIT	DEFICIENCIES
80	27.3	17.5	61	2.5	-
100	26.2	17.5	64	1.3	1
125	25.4	11.8	66	1.0	3
160	22.1	12.0	66	0.9	3
200	22.8	10.6	67	0.7	4
250	32.9	11.5	64	0.7	1
315	18.2	10.7	64	0.5	1
400	20.3	8.6	62	0.4	0
500	21.1	7.8	62	0.2	1
630	18.2	7.7	62	0.4	2
800	18.8	7.2	63	0.4	4
1000	16.1	7.2	60	0.4	2
1250	13.9	7.2	55	0.5	0
1600	12.8	7.6	50	0.2	0
2000	11.0	8.5	51	0.4	2
2500	11.8	9.4	48	0.3	2
3150	11.9	10.6	43	0.2	0
4000	10.9	12.1	37	0.2	-
5000	10.9	14.0	33	0.4	-
6300	11.4	18.2	28	0.5	-
8000	12.3	23.8	23	0.8	-
10000	12.5	30.2	20	0.9	-
IIC Rating	49	(Impact Insulati	on Class)	Sum of Deficiencies	26

Notes: Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP


Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 13

TEST RESULTS - IMPACT SOUND TRANSMISSION GRAPH

TEST DATE DATA FILE NO. CLIENT	2/17/2018 H7787.12 Vulcraft/Verco	•				
DESCRIPTION	4000 PSI Concrete	5 mm Daltile Ceramic Tile, 5 mm ECOsilence Rubber Underlayment, 152.4 mm Standard 2000 PSI Concrete, 152.4 mm 20 Gage Vulcraft Dove Tail 3.50 Steel Deck, 38.1 mm arkDietrich 25 Gage Furring Channel, 15.9 mm USG SHEETROCK® Brand FIRECODE® C				
SPECIMEN AREA	10.98 m²	.98 m ² Maximum Temp. 18.9°C Minimum Temp. 18.9°C				
TECHNICIAN	JPT	Max. Humidity	57%	Min. Humidity	56%	





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 14

PHOTOGRAPHS



Photo No. 1 Source Room View of Test Specimen Installation



Photo No. 2
Receive Room View of Test Specimen Installation



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 15

DRAWING



Drawing of Test Specimen (supplied by Client)



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7787.12-113-11-R0

Date: 04/05/18

SECTION 16

REVISION LOG

REVISION #	DATE	PAGES	DESCRIPTION
RO	04/05/18	N/A	Original Report Issue