

VULCRAFT/VERCO GROUP ACOUSTICAL PERFORMANCE TEST REPORT

SCOPE OF WORK

ASTM E90 AND ASTM E492 TESTING ON CERAMIC TILE OVER 5 MM ECOSILENCE UNDERLAYMENT

SPECIMEN TYPE

Vulcraft 20 Gage Dove Tail 2.00 Steel Deck

REPORT NUMBER

H7786.06-113-11-R2

TEST DATE

02/12/18

 ISSUE DATE
 REVISED DATE


 03/22/18
 08/10/18

RECORD RETENTION END 02/12/22

PAGES

13

DOCUMENT CONTROL ATI 00629 (09/19/17) RTTDS-R-AMER-Test-2844 © 2017 INTERTEK





130 Derry Court York, PA 17406

Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

REPORT ISSUED TO

VULCRAFT/VERCO GROUP 7205 Gault Avenue North Fort Payne, Alabama 35967

SECTION 1

SCOPE

Intertek Building & Construction (B&C) was contracted by to perform testing in accordance with ASTM E90 AND ASTM E492 on Ceramic Tile over 5 mm ECOsilence Underlayment. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted in the VT test chambers at Intertek B&C located in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

SECTION 2

SUMMARY OF TEST RESULTS

DATA FILE NO.	H7786.06
SERIES/MODEL:	Ceramic Tile over 5 mm ECOsilence Underlayment
STC	51
IIC	41

COMPLETED BY:	Daniel B. Mohler	COMPLETED BY:	Jordan Strybos
	Project Lead - Acoustical		Project Manager - Acoustical
TITLE:	Testing	TITLE:	Testing
SIGNATURE:		SIGNATURE:	
DATE:	08/10/18	DATE:	08/10/18

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of ACCREDITED the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.



Testing Laboratory



TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 3 TEST METHODS

The specimen was evaluated in accordance with the following:

ASTM E90-09 (2016), Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

ASTM E413-16, Classification for Rating Sound Insulation

ASTM E492-09(2016)e1, Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine

ASTM E989-06 (2012), Classification for Determination of Impact Insulation Class (IIC)

ASTM E2235-04 (2012), Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods

SECTION 4

MATERIAL SOURCE/INSTALLATION

The full test specimen was assembled on the day of testing by B&C. All materials provided by the client were installed on an existing B&C assembly (Vulcraft 20 Gage Dove Tail 2.00 Steel Deck) utilizing B&C-supplied materials. The assembly was installed in a steel test frame which was installed into the opening between the source and receive rooms in the test chamber. The test frame was isolated from the structure with dense neoprene gasket.

The total weight of the floor/ceiling assembly was 3074.7 kg. B&C will store samples of the test specimen for four years. Photographs of the test specimen are included in the attachments. A drawing of the test specimen is included in the attachments.

B&C will service this report for the entire test record retention period. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by B&C for the entire test record retention period.



Total Quality. Assured.

Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 5

EQUIPMENT

INSTRUMENT	MANUFACTURER	MODEL	DESCRIPTION	ASSET #	CAL DA	TE
Data Acquisition Unit	National Instruments	PXI-1033	Data Acquisition Card	63763-1	06/16	*
Data Acquisition Unit	National Instruments	PXI-4462	Input Card	63763-4	07/16	*
Data Acquisition Unit	National Instruments	PXI-4462	Input Card	63763-5	06/16	*
Microphone Calibrator	Norsonic	1251	Pistonphone calibrator	INT00127	03/17	
Receive Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	65617	05/17	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63744	05/17	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63745	05/17	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63746	09/17	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63747	05/17	
Receive Room Environmental	Comet	T7510	Temperature and Humidity	63810	10/17	
Indicator	comet	1/510	Transmitter	63811	10/17	
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63738	04/17	
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63739	04/17	
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63740	04/17	
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63742	04/17	
Source Room Microphone	PCB Electronics	378B20	Microphone and Preamplifier	63741	04/17	
Source Room Environmental Indicator	Comet	T7510	Temperature and Humidity Transmitter	INT00603	03/17	
Tapping Machine	Norsonic	Nor277	Tapping Machine	INT00936	12/17	

* The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

VT RECEIVE ROOM VOLUME	158.99 m³
VT SOURCE ROOM VOLUME	190 m ³

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Daniel B. Mohler	Intertek B&C
Jordan Strybos	Intertek B&C



TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 7 TEST PROCEDURE

The microphones were calibrated before conducting the tests. The air temperature and relative humidity conditions were monitored and recorded during all measurements.

The airborne transmission loss test was conducted in accordance with the ASTM E90 test method using the single direction method. Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions. Four sound pressure level measurements were made simultaneously in both rooms, at each of five microphone positions.

The impact sound transmission test was conducted in accordance with the ASTM E492 test method. Two background noise sound pressure level, two sound pressure level measurements with the tapping machine operating at each position specified by ASTM E492, and five sound absorption measurements were conducted at each of five microphone positions.

Detailed test procedures, data for flanking limit tests, repeatability measurements, and reference specimen tests are available upon request.

SECTION 8 TEST CALCULATIONS

The STC (Sound Transmission Class) and IIC (Impact Insulation Class) ratings were calculated in accordance with ASTM E413 and ASTM E989, respectively.



TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 9

TEST SPECIMEN DESCRIPTION

MATERIAL	DIMENSIONS (mm/inch)	THICKNESS (mm/inch)	MANUFACTURER AND SERIES	QUANTITY	AVERAGE WEIGHT				
	304.8 by 304.8	8.5	Daltile	10.98 m²	15.72 kg/m²				
Ceramic Tile	Note: Laticrete Permacolor grout was placed into the 6.35 mm joints between the porcelain tile and wiped clean. The ceramic tile was placed with light pressure onto a bed of Laticrete Platinum 254 mortar on the underlayment. The mortar was set using a 6.35 mm by 6.35 mm trowel. Both the grout and mortar were allowed to cure to manufacturer's specifications.								
	3023 by 1219	5.0	ECOsilence	10.98 m²	4.2 kg/m²				
Rubber Underlayment	adhesive. The und was spread using	Note: A sheet of 2 mil polyethylene plastic was adhered to the floor slab with 3M Super 77 spray adhesive. The underlayment was adhered to the sheeting with ECORE™ EGrip™ III adhesive, which was spread using a 0.79 mm by 1.59 mm by 0.79 mm trowel. Adhesive was allowed to cure per manufacturer's specifications.							
Standard 4000	3023 by 3632	139.7	N/A	10.98 m²	248.08 kg/m²				
PSI Concrete	Note: Poured directly on the floor deck and allowed to cure for a minimum of 28 days.								
	3023 by 609.6	139.7	20 Gage Vulcraft Dove Tail 2.00	10.98 m²	12.01 kg/m²				
Steel Deck	Note: Installed per manufacturer's specifications in a test frame with the top of the concrete flush with the source room. All seams and gaps underneath the deck were plugged with backer rod and sealed with Pecora AC-20 Acoustical Sealant.								



TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 10

TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS



TEST DATE	2/12/2018				ACCREDITED	
DATA FILE NO.	H7786.06	17786.06				
CLIENT	Vulcraft/Verco	ulcraft/Verco Group				
DESCRIPTION		eramic Tile, 5 mm ECOsi e, 139.7 mm 20 Gage Vi			7 mm Standard	
SPECIMEN AREA	10.98 m²	Receive Temp.	17.6°C	Source Temp.	18.9°C	
TECHNICIAN	ZPG	Receive Humidity	60%	Source Humidity	60%	

	BACKGROUND		SOURCE	RECEIVE	SPECIMEN	95%	NUMBER
FREQ	SPL	ABSORPTION	SPL	SPL	TL	CONFIDENCE	OF
(Hz)	(dB)	m²	(dB)	(dB)	(dB)	LIMIT	DEFICIENCIES
80	38.7	17.0	110	68	40	3.8	-
100	30.7	14.3	106	66	39	3.0	-
125	30.0	10.8	105	67	38	1.3	0
160	29.5	11.1	107	69	38	0.9	0
200	23.6	11.4	105	68	37	1.9	4
250	23.0	11.7	104	64	39	1.1	5
315	24.4	11.3	105	61	44	1.0	3
400	21.6	8.5	104	57	48	0.6	2
500	22.4	8.5	103	56	48	0.5	3
630	24.4	8.2	104	61	44	0.7	8
800	23.6	7.5	103	55	51	0.5	2
1000	21.6	7.6	104	51	54	0.6	0
1250	18.3	7.8	103	50	54	0.5	1
1600	14.6	7.7	103	46	58	0.4	0
2000	10.0	8.6	103	44	61	0.4	0
2500	6.5	9.8	102	39	63	0.4	0
3150	5.5	10.8	103	34	69	0.4	0
4000	5.3	12.8	104	32	71	0.4	0
5000	5.4	15.6	104	30	73	0.5	-
6300	6.0	20.3	98	18	76	0.7	-
8000	6.5	26.9	97	14	79	0.9	-
10000	6.6	34.3	93	8	80	0.9	-
STC Rati	ng 51	(Sound Transm	ission Class)		Sum	of Deficiencies	28

Notes:

1) Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.

2) Specimen TL levels listed in red are potentially limited by the laboratory flanking limit.

3) Specimen TL levels listed in *blue* indicate the lower limit of the transmission loss.

4) Specimen TL levels listed in green indicate that there has been a filler wall correction applied



TEST REPORT FOR VULCRAFT/VERCO GROUP


Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 11

TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS GRAPH



TEST DATE	2/12/2018				ACCREDITED	
DATA FILE NO.	H7786.06	Testing				
CLIENT	Vulcraft/Verco	Group			Laboratory	
DESCRIPTION	8.5 mm Daltile Ceramic Tile, 5 mm ECOsilence Rubber Underlayment, 139.7 mm Standard 4000 PSI Concrete, 139.7 mm 20 Gage Vulcraft Dove Tail 2.00 Steel Deck					
SPECIMEN AREA	10.98 m²	Receive Temp.	17.6°C	Source Temp.	18.9°C	
TECHNICIAN	ZPG	Receive Humidity	60%	Source Humidity	60%	





TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 12

TEST RESULTS - IMPACT SOUND TRANSMISSION



TEST DATE	2/12/2018				ACCREDITED
DATA FILE NO.	H7786.06	17786.06			
CLIENT	Vulcraft/Verco	Group			Testing Laboratory
DESCRIPTION		eramic Tile, 5 mm ECOsi e, 139.7 mm 20 Gage Vi		, ,	7 mm Standard
SPECIMEN AREA	10.98 m²	Maximum Temp.	17.8°C	Minimum Temp.	17.4°C
TECHNICIAN	ZPG	Max. Humidity	60%	Min. Humidity	60%

FREQ	BACKGROUND SPL	ABSORPTION	NORMALIZED IMPACT SP	L 95% CONFIDENCE	NUMBER OF
(Hz)	(dB)	m²	(dB)	LIMIT	DEFICIENCIES
80	38.3	17.5	57	2.0	-
100	30.1	13.8	58	1.2	0
125	29.6	10.5	57	1.2	0
160	28.2	11.7	65	1.1	0
200	24.2	11.8	68	0.7	0
250	23.5	11.3	69	0.7	0
315	24.2	10.7	71	0.5	0
400	20.9	8.6	68	0.3	0
500	22.2	8.4	72	0.5	3
630	23.8	8.3	76	0.3	8
800	23.6	7.4	72	0.4	5
1000	23.1	7.5	66	0.5	0
1250	20.0	7.8	61	0.5	0
1600	15.7	7.8	57	0.2	0
2000	10.9	8.6	54	0.4	0
2500	6.6	9.8	51	0.3	0
3150	5.4	10.8	46	0.3	0
4000	5.3	12.8	43	0.4	-
5000	5.4	15.6	43	0.5	-
6300	6.0	20.0	37	0.5	-
8000	6.4	26.6	35	0.4	-
10000	6.6	33.9	35	0.6	-
IIC Ratii	<mark>1g</mark> 41	(Impact Insulat	tion Class)	Sum of Deficiencies	16

Notes: Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



TEST REPORT FOR VULCRAFT/VERCO GROUP


Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 13

TEST RESULTS - IMPACT SOUND TRANSMISSION GRAPH



TEST DATE DATA FILE NO. CLIENT	2/12/2018 H7786.06 Vulcraft/Verco Group				ACCREDITED" Testing Laboratory		
DESCRIPTION	8.5 mm Daltile Ce	Autoratt/Verco Group 3.5 mm Daltile Ceramic Tile, 5 mm ECOsilence Rubber Underlayment, 139.7 mm Standard 4000 PSI Concrete, 139.7 mm 20 Gage Vulcraft Dove Tail 2.00 Steel Deck					
SPECIMEN AREA	10.98 m²	Maximum Temp.	17.8°C	Minimum Temp.	17.4°C		
TECHNICIAN	ZPG	Max. Humidity	60%	Min. Humidity	60%		





130 Derry Court York, PA 17406

Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 14

PHOTOGRAPHS



Photo No. 1 Source Room View of Test Specimen Installation




Photo No. 2 Receive Room View of Test Specimen Installation



130 Derry Court York, PA 17406

Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


Total Quality. Assured.

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 15

DRAWING



Drawing of Test Specimen (supplied by Client)



Total Quality. Assured.

Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR VULCRAFT/VERCO GROUP

Report No.: H7786.06-113-11-R2 Date: 08/10/18

SECTION 16

REVISION LOG

REVISION #	DATE	PAGES	DESCRIPTION
RO	03/22/18	N/A	Original Report Issue
R1	04/04/18	1, 6-10, 12	Steel deck name adjusted and drawing updated per client's request
R2	08/10/18	All pages	Dataset number corrected, specimen type corrected